

EMC Test Report

According to

Test Standard : EN IEC 61000-6-4:2019, IEC 61000-6-4:2018
EN IEC 61000-6-2:2019, IEC 61000-6-2:2016
EN IEC 61000-3-2:2019, IEC 61000-3-2:2018
EN 61000-3-3:2013+A1:2019, IEC 61000-3-3:2013+A1:2017

Equipment : MPPT SOLAR INVERTER
Model Number : VM IV-3600
Serial model : --
Applicant : Voltronic Power Technology Corp.
No. 406, Xinhu 1st Road, Neihu District, Taipei, Taiwan,
R.O.C.

Test date : Mar 18, 2021 ~ Mar 21, 2021
Issue date : Mar 30, 2021

Statement:

- The test result is applied to test equipment unit (EUT) only.
- Without written approval of SERTC Testing Center Co., Ltd the test report shall not be reproduced except in full.

Rack Chiang

Rack Chiang/ /Approved Signatory



SERTC Testing Center Co., Ltd

No.230, Sec. 2, Fengshi Rd., Fengyuan Dist., Taichung City 420, Taiwan, R.O.C.

History of this test report

Report No.	Version	Description	Issue Date
21123CEAE1	Rev.1.0	Initial issue of report	Mar 30,2021

Contents

1. General Description	6
1.1 Application category	6
1.2 Applied standards	6
1.3 Basic Description of Equipment under Test	7
1.4 The I/O ports of EUT are listed below :	7
2. Test configuration of EUT.....	8
2.1 Test Manner	8
2.2 General requirement of test	8
2.3 Layout of the Setup.....	9
2.4 Test software	11
2.5 Immunity Testing Performance Criteria Definition	11
2.6 General Information of Test	12
3. Conducted Emission Measurement.....	14
3.1 Limits for Emission Measurement.....	14
3.2 Test Procedures.....	15
3.3 Test Configurations	16
3.4 Photographs of the Test Configurations – Charge mode and stored energy mode	17
3.5 Photographs of the Test Configurations – PV mode	18
3.6 Test Results and data	19
4. Radiated Emission Measurement	25
4.1 Limits for Emission Measurement.....	25
4.2 Test Procedures.....	27
4.3 Test Configurations	28
4.4 Photographs of the Test Configurations– Charge mode and stored energy mode	29
4.5 Photographs of the Test Configurations– PV mode	30
4.6 Test Results and data	31
5. Harmonic Current Emission Measurement	37
5.1 Limits for Emission Measurement.....	錯誤! 尚未定義書籤。
5.2 Test Procedures.....	錯誤! 尚未定義書籤。

5.3	Test Configurations	39
5.4	Photographs of the Test Configurations	39
5.5	Test Results and data	40
6.	Voltage Fluctuations and Flickers Emission Measurement	42
6.1	Limits for Emission Measurement.....	42
6.2	Test Procedures.....	43
6.3	Test Configurations	44
6.4	Photographs of the Test Configurations.....	44
6.5	Test Results and data	45
7.	Electrostatic Discharge (ESD) Immunity Test	46
7.1	Specifications of Immunity Test Requirement	46
7.2	Test Severity Levels.....	47
7.3	Test Procedures.....	48
7.4	Test Configurations	50
7.5	Photographs of the Test Configurations.....	50
7.6	Test Results	51
7.7	Photographs of the Test Points on the EUT for ESD Test.....	53
8.	Radiated Electromagnetic Field (RS) Immunity Test	56
8.1	Test Requirement	56
8.2	Test Severity Level.....	56
8.3	Test Procedures.....	57
8.4	Test Configurations	58
8.5	Photographs of the Test configurations.....	58
8.6	Test Result and Data	59
9.	Electrical fast transient / burst (EFT) Immunity Test	60
9.1	Test Procedure	60
9.2	Test Severity Levels.....	61
9.3	Test Configurations	61
9.4	Photographs of the Test Configurations.....	62
9.5	Test Result and Data	63
10.	Surge Immunity Test.....	64

10.1	Test Procedure	64
10.2	Test Severity Level.....	65
10.3	Test Configurations.....	65
10.4	Photographs of the Test Configurations.....	66
10.5	Test Result and Data	67
11.	Conducted disturbances (CS) Immunity Test	68
11.1	Test Procedure	68
11.2	Test Severity Levels.....	69
11.3	Test Configurations.....	69
11.4	Photographs of the Test Configurations.....	70
11.5	Test Result and Data	71
12.	Power frequency magnetic field (PFM) Immunity Test.....	72
12.1	Test Procedure	72
12.2	Test Severity Levels.....	73
12.3	Test Configurations.....	73
12.4	Photographs of the Test Configurations.....	74
12.5	Test Result and Data	75
13.	Voltage Dips and Voltage Interruptions Immunity	76
13.1	Test procedure.....	76
13.2	Test severity.....	77
13.3	Test Configurations.....	77
13.4	Photographs of the Test Configurations.....	78
13.5	Test Result and data.....	79
14.	List of Measuring Equipment.....	80
15.	Measurement Uncertainty	83
16.	Attachment 1 – Photographs of EUT	84

1. General Description

1.1 Application category

<input checked="" type="checkbox"/> New application	This document is new applicant.
<input type="checkbox"/> Copy report	This document originally test result as : · Issue unit : · Report number :
<input type="checkbox"/> Application for change	Addition of series or others. · Original Report number :

1.2 Applied standards

According to the specifications of the manufacturer and the requirements set in European Council EMC Directive 2014/30/EU, the applied standards to evaluate the compliance of the EUT are as following:

Applied Standards	Test Items	Results
EN IEC 61000-6-4:2019 IEC 61000-6-4:2018	Conducted Emission Measurement 150k-30MHz	<u>Complied</u>
	Radiated Emission Measurement 30M- 1GHz	<u>Complied</u>
EN IEC 61000-3-2:2019 IEC 61000-3-2:2018	Harmonic Current Emission Measurement	<u>Complied</u>
EN 61000-3-3:2013+A1:2019 IEC 61000-3-3:2013+A1:2017	Voltage Fluctuation and Flicker Emission Measurement	<u>Complied</u>
EN IEC 61000-6-2:2019, IEC 61000-6-2:2016		
EN 61000-4-2:2009 IEC 61000-4-2:2008	Electrostatic discharge Test (ESD)	<u>Complied</u>
EN 61000-4-3:2006+A2:2010 IEC 61000-4-3:2006+A1:2007+A2:2010	Radiated electromagnetic field immunity Test (RS)	<u>Complied</u>
EN 61000-4-4:2012 IEC 61000-4-4:2012	Electrical fast transient / burst immunity Test (EFT)	<u>Complied</u>
EN 61000-4-5:2014+A1:2017 IEC 61000-4-5:2014+A1:2017	Surge immunity Test	<u>Complied</u>
EN 61000-4-6:2014 IEC 61000-4-6:2013	Immunity to conducted disturbances, induced by radio-frequency fields (CS)	<u>Complied</u>
EN 61000-4-8:2010 IEC 61000-4-8:2009	Power frequency magnetic field immunity Test (PFM)	<u>Complied</u>
IEC 61000-4-34:2009 EN 61000-4-34:2007+A1:2009	Voltage dips, short interruptions Test	<u>Complied</u>

1.3 Basic Description of Equipment under Test

Equipment	MPPT SOLAR INVERTER
Trade Name	N/A
Model Number	VM IV-3600
Serial model	--
Power Supply Type	Battery Input: 24Vdc. AC Input:230V. PV:400Vdc. AC Output: 230V/50Hz Max, 3600VA/3600W, 1 § +PE
Highest Operating Frequency	19.2K
Function description	The EUT is an engineer sample of the MPPT SOLAR INVERTER. Please refer to the user's manual for the details.

1.4 The I/O ports of EUT are listed below :

No.	Port Type	Quantity
1	AC input port	1
2	AC output port	1
3	DC port (+,-)	1
4	PV port (+,-)	1
5	RJ45 (RS-232/RS-485) port	2
6	Micro USB port	1
7	Dry contact	1

2. Test configuration of EUT

2.1 Test Manner

- a. During testing, the interface cables and equipment positions were varied according to Europe Standard EN 61000-6-2 and EN 61000-6-4

Conducted Emission for AC main power	
Test Mode 1	Charge and normal mode, full load
Test Mode 2	Stored Energy mode, full load
Test Mode 3	PV mode, full load
Radiated Emissions for below 1GHz	
Test Mode 1	Charge and normal mode, full load
Test Mode 2	Stored Energy mode, full load
Test Mode 3	PV mode, full load
Harmonic and Flicker Emissions	
Test Mode 1	Charge and normal mode, full load
Immunity Test (ESD, RS, EFT, SURGE, CS, PFM, DIP)	
Test Mode 1	Charge and normal mode, full load


2.2 General requirement of test

The EUT is an unique unit connected with other necessary accessories and support units listed in the next section. It has been tested against each standard after the following setup steps:

- a. Connect the Dummy Load to the EUT.
- b. Connect the EUT to the appropriate power source through power filter or other LISN in different site for each test item.
- c. Set the Dummy Load at the assigned condition.
- d. According to the setup methods designated by its manufacturer, set the EUT in the operating condition.
- e. Repeat and keep the setup steps listed above before and during all tests.

2.3 Layout of the Setup


PV mode for Radiated emission and conducted emission test



The Support Units:

No.	Link Peripheral	Manufacturer	Model No.	FCC ID	Description of connected
For Local					
1	Main AC input	--	--	--	A , non-shield cable Length 1.8m
2	Battery pack	--	--	--	B, non-shield cable Length 0.5 m
3	Light bulb load	--	--	--	C, non-shield cable Length 1.0 m
4	DC supply unit	--	--	--	D, non-shield cable Length 10 m

Charge mode and Stored energy mode for all test



The Support Units:

No.	Link Peripheral	Manufacturer	Model No.	FCC ID	Description of connected
For Local					
1	Main AC input	--	--	--	A , non-shield cable Length 1.8m
2	Battery pack	--	--	--	B, non-shield cable Length 0.5 m
3	Light bulb load	--	--	--	C, non-shield cable Length 1.0 m

2.4 Test software

The EUT no needs to control by others software.

2.5 Immunity Testing Performance Criteria Definition


- a) **Performance criterion A:** The EUT shall continue to operate as intended during and after the test. No degradation of performance or loss of function is allowed below a performance level specified by the manufacturer, when the EUT is used as intended. If the performance level is not specified by the manufacturer, this may be derived from the product description and documentation and what the user may reasonably expect from the equipment if used as intended.
- b) **Performance criterion B:** The EUT shall continue to operate as intended after the test. No degradation of performance or loss of function is allowed below a performance level specified by the manufacturer, when the EUT is used as intended. The performance level may be replaced by a permissible loss of performance. However, during the test degradation of performance is allowed but no change of actual operating state or stored data is allowed. If the minimum performance level or the permissible performance loss is not specified by the manufacturer, either of these may be derived from the product description and documentation and what the user may reasonably expect from the equipment if used as intended.
- c) **Performance criterion C:** Temporary loss of function is allowed during the test, provided the function is self-recoverable or can be restored by the operation of the controls.

2.6 General Information of Test

Location of test laboratory

SERTC testing Laboratory	Accreditations
Address: No. 230, Sec. 2, Fengshi Rd., Fengyuan Dist., Taichung City 420, Taiwan, R.O.C. Tel: +886-04-25253313 Fax:+886-04-25252320	TAF No. 3625

The map shows location of the SERTC Testing Laboratory proximity to the Tai-Chung city as below:



Test Facility

The test facility used for evaluating the conformance of the EUT with each standard in the present report meets what required in CISPR16-1-4,ANSI,C63.4:2014+ANSI C63.4a:2017.

Test Room	Type of Test Room	Descriptions
CB1	3m semi-anechoic chamber	Complying with the NSA and the site VSWR requirements in documents CISPR 16-1-4 and ANSI C63.4:2014+ANSI C63.4a:2017, for the radiated emission measurements, and Radiated susceptibility test.
CB2	Shielding Room	For the conducted emission measurement.
TR1	Plane Grounding Site	For the conducted susceptibility test.
TR2	Plane Grounding Site	For the Current Harmonic / Voltage Flicker and other immunity tests.
TR3	Plane Grounding Site	For the Surge, Electrical fast transient and Power frequency magnetic field immunity test.

3. Conducted Emission Measurement

3.1 Limits for Emission Measurement

Conducted Emissions were measured from 150 kHz to 30 MHz with a bandwidth of 9 kHz and return leads of the EUT according to the methods defined in European Standard IEC61000-6-4. The EUT was placed on a nonmetallic stand in a shielded room 0.8 meters above the ground plane. The interface cables and equipment positioning were varied within limits of reasonable applications to determine the position producing maximum conducted emissions.

Table 1 Conducted Emission Limits(dB μ V):

Frequency range (MHz)	AC main port		DC port	
	Quasi Peak	Average	Quasi Peak	Average
0.15 to0.50	79	66	89	76
0.50 to5	73	60	83	70
5. to 30.	73	60	83	70

Note 1: The lower limits shall apply at the transition frequencies.
 Note 2: The limit decreases linearly with the logarithm of the frequency in the range 0.15 MHz to 0.5MHz.

Table 2 - Limits of conducted common mode (asymmetric mode) disturbance in the frequency range 0.15 MHz to 30 MHz (dB μ V).


Frequency range (MHz)	Wired network port			
	Voltage		Current	
	Quasi Peak	Avg.	Quasi Peak	Avg.
0.15 to 0.5	97~ 87	84~74	53~43	40~30
0.5 to 5	87	74	43	30
5 to 30	87	74	43	30

Note 1: The limits decrease linearly with the logarithm of the frequency in the range 0.15 to 0.5 MHz.
 Note 2 : The current and voltage disturbance limits are derived for use with an impedance stabilization network (ISN) which presents a common mode (asymmetric mode) impedance of 150 Ω to the telecommunication under test (conversion factor is $20 \log_{10} 150/1 = 44\text{dB}$).

3.2 Test Procedures


- a. The EUT was set up per the test configuration figured in the next section of this chapter to simulate the typical usage per the user's manual.
- b. If the EUT is tabletop equipment, it was placed on a wooden table with a height of 0.8 meters above the reference ground plane and 0.4 meters from the conducting wall of the shielded room. Also if the EUT is floor-standing equipment, it was placed on a non-conducted support with a height up to 0.15 meters above the reference ground plane.
- c. Connect the EUT's power source / telecommunication lines to the appropriate power mains / peripherals through the LISN / ISN.
- d. All the other peripherals are connected to the 2nd LISN, if any.
- e. The LISN / ISN was placed 0.8 meters from the EUT and at least 0.8 meters from other units and other metal planes.
- f. Measure the conducted emissions on each power line (Neutral Line and Line 1 – Hot side) of the EUT's power source by using the test receiver connected to the coupling RF output port of LISN.
- g. Rapidly scan the signal from 150kHz to 30MHz by using the receiver through the Maximum-Peak detector to determine those frequencies associated with higher emission levels for each measured line.
- h. Then measure the maximum level of conducted disturbance for each frequency found from step g. by using the receiver through the Quasi-Peak and Average detectors per CISPR 16-1.
- i. Record the level for each frequency and compare with the required limit.
- j. If required, measure the conducted emissions on telecommunication lines of EUT by using the test receiver connected to the coupling RF output port of ISN and repeat step g. to i.
- k. If the peak emission level is lower than the specified Average limit, then the emission values presented will be the peak value only. Otherwise, accurate Q.P. or Average values will be measured and presented.

3.3 Test Configurations




Example measurement arrange for table-top EUT

3.4 Photographs of the Test Configurations – Charge mode and stored energy mode



3.5 Photographs of the Test Configurations – PV mode




3.6 Test Results and data

Conducted Emission for Power Port Test Data

Test Mode	Mode 1	Pol/Phase	Line1
Test Frequency	0.15 MHz ~ 30 MHz	Test Voltage	230Vac/50Hz
Test Date	Mar 18,2021	Test Engineer	David
Temperature	22 °C	Relative Humidity	67%

Note:

1. Emission Level = reading value + correction factor.
2. Correction factor = cable loss + insertion loss of LISN.
3. Q.P. is abbreviation of quasi-peak.
4. If the limit for the measurement with the average detector is met when using a receiver with a quasi-peak detector, the EUT shall be deemed to meet both limits.




	Freq	Read Level	Factor	Level	Limit Line	Over Limit	Pol/Phase	Remark
	MHz	dBuV	dB	dBuV	dBuV	dB		
1	0.151	34.81	10.23	45.04	66.00	-20.96	line1	Average
2 QP	0.151	64.10	10.23	74.33	79.00	-4.67	line1	QP
3	0.185	53.54	10.22	63.76	66.00	-2.24	line1	Average
4	0.185	61.44	10.22	71.66	79.00	-7.34	line1	QP
5	0.211	26.89	10.22	37.11	66.00	-28.89	line1	Average
6	0.211	57.67	10.22	67.89	79.00	-11.11	line1	QP
7	0.240	40.30	10.22	50.52	66.00	-15.48	line1	Average
8	0.240	54.38	10.22	64.60	79.00	-14.40	line1	QP
9	0.255	35.57	10.22	45.79	66.00	-20.21	line1	Average
10	0.255	55.03	10.22	65.25	79.00	-13.75	line1	QP
11	0.300	42.01	10.21	52.22	66.00	-13.78	line1	Average
12	0.300	50.42	10.21	60.63	79.00	-18.37	line1	QP
13	0.326	46.36	10.21	56.57	66.00	-9.43	line1	Average
14	0.326	50.52	10.21	60.73	79.00	-18.27	line1	QP
15	0.379	43.78	10.21	53.99	66.00	-12.01	line1	Average
16	0.379	47.69	10.21	57.90	79.00	-21.10	line1	QP
17	0.418	44.02	10.21	54.23	66.00	-11.77	line1	Average
18	0.418	48.34	10.21	58.55	79.00	-20.45	line1	QP
19	0.501	45.77	10.21	55.98	60.00	-4.02	line1	Average
20	0.501	46.51	10.21	56.72	73.00	-16.28	line1	QP
21	4.790	38.62	10.49	49.11	60.00	-10.89	line1	Average
22	4.790	46.28	10.49	56.77	73.00	-16.23	line1	QP
23 PP	20.971	46.91	11.97	58.88	60.00	-1.12	line1	Average
24	20.971	51.19	11.97	63.16	73.00	-9.84	line1	QP

Test Mode	Mode 1	Pol/Phase	Neutral
Test Frequency	0.15 MHz ~ 30 MHz	Test Voltage	230Vac/50Hz
Test Date	Mar 18,2021	Test Engineer	David
Temperature	22 °C	Relative Humidity	67%

Note:

1. Emission Level = reading value + correction factor.
2. Correction factor = cable loss + insertion loss of LISN.
3. Q.P. is abbreviation of quasi-peak.
4. If the limit for the measurement with the average detector is met when using a receiver with a quasi-peak detector, the EUT shall be deemed to meet both limits.




	Freq	Read Level	Factor	Level	Limit Line	Over Limit	Pol/Phase	Remark
	MHz	dBuV	dB	dBuV	dBuV	dB		
1	0.151	36.35	10.24	46.59	66.00	-19.41	neutral	Average
2	0.151	65.43	10.24	75.67	79.00	-3.33	neutral	QP
3	0.186	53.40	10.23	63.63	66.00	-2.37	neutral	Average
4	0.186	59.20	10.23	69.43	79.00	-9.57	neutral	QP
5	0.211	26.35	10.22	36.57	66.00	-29.43	neutral	Average
6	0.211	55.80	10.22	66.02	79.00	-12.98	neutral	QP
7	0.230	52.32	10.22	62.54	66.00	-3.46	neutral	Average
8	0.230	59.35	10.22	69.57	79.00	-9.43	neutral	QP
9	0.245	35.21	10.22	45.43	66.00	-20.57	neutral	Average
10	0.245	56.22	10.22	66.44	79.00	-12.56	neutral	QP
11	0.274	49.22	10.22	59.44	66.00	-6.56	neutral	Average
12	0.274	53.73	10.22	63.95	79.00	-15.05	neutral	QP
13	0.285	37.68	10.22	47.90	66.00	-18.10	neutral	Average
14	0.285	50.58	10.22	60.80	79.00	-18.20	neutral	QP
15	0.303	39.86	10.22	50.08	66.00	-15.92	neutral	Average
16	0.303	51.99	10.22	62.21	79.00	-16.79	neutral	QP
17	0.482	47.25	10.22	57.47	66.00	-8.53	neutral	Average
18	0.482	48.32	10.22	58.54	79.00	-20.46	neutral	QP
19	6.168	40.33	10.72	51.05	60.00	-8.95	neutral	Average
20	6.168	48.25	10.72	58.97	73.00	-14.03	neutral	QP
21	19.747	41.80	12.49	54.29	60.00	-5.71	neutral	Average
22	19.747	46.21	12.49	58.70	73.00	-14.30	neutral	QP
23	21.118	42.84	12.65	55.49	60.00	-4.51	neutral	Average
24	21.118	46.54	12.65	59.19	73.00	-13.81	neutral	QP

Test Mode	Mode 2	Pol/Phase	Line 1
Test Frequency	0.15 MHz ~ 30 MHz	Test Voltage	230Vac/50Hz
Test Date	Mar 18,2021	Test Engineer	David
Temperature	22 °C	Relative Humidity	67%

Note:

1. Emission Level = reading value + correction factor.
2. Correction factor = cable loss + insertion loss of LISN.
3. Q.P. is abbreviation of quasi-peak.
4. If the limit for the measurement with the average detector is met when using a receiver with a quasi-peak detector, the EUT shall be deemed to meet both limits.




	Freq	Read Level	Factor	Limit Level	Over Limit	Pol/Phase	Remark
	MHz	dBuV	dB	dBuV	dB		
1	0.184	28.90	10.22	39.12	66.00	-26.88	line1 Average
2	0.184	33.39	10.22	43.61	79.00	-35.39	line1 QP
3	0.426	20.76	10.21	30.97	66.00	-35.03	line1 Average
4	0.426	29.90	10.21	40.11	79.00	-38.89	line1 QP
5	0.501	26.87	10.21	37.08	60.00	-22.92	line1 Average
6	0.501	35.60	10.21	45.81	73.00	-27.19	line1 QP
7	4.413	36.52	10.45	46.97	60.00	-13.03	line1 Average
8	4.413	44.51	10.45	54.96	73.00	-18.04	line1 QP
9 PP	19.348	46.03	11.82	57.85	60.00	-2.15	line1 Average
10 QP	19.348	50.27	11.82	62.09	73.00	-10.91	line1 QP
11	20.173	43.57	11.90	55.47	60.00	-4.53	line1 Average
12	20.173	48.38	11.90	60.28	73.00	-12.72	line1 QP

Test Mode	Mode 2	Pol/Phase	Neutral
Test Frequency	0.15 MHz ~ 30 MHz	Test Voltage	230Vac/50Hz
Test Date	Mar 18,2021	Test Engineer	David
Temperature	22 °C	Relative Humidity	67%

Note:

1. Emission Level = reading value + correction factor.
2. Correction factor = cable loss + insertion loss of LISN.
3. Q.P. is abbreviation of quasi-peak.
4. If the limit for the measurement with the average detector is met when using a receiver with a quasi-peak detector, the EUT shall be deemed to meet both limits.




	Read Freq	Level	Factor	Level	Limit Line	Over Limit	Pol/Phase	Remark
	MHz	dBuV	dB	dBuV	dBuV	dB		
1	0.179	33.36	10.23	43.59	66.00	-22.41	neutral	Average
2	0.179	39.91	10.23	50.14	79.00	-28.86	neutral	QP
3	0.420	40.39	10.22	50.61	66.00	-15.39	neutral	Average
4	0.420	42.78	10.22	53.00	79.00	-26.00	neutral	QP
5	4.524	35.44	10.56	46.00	60.00	-14.00	neutral	Average
6	4.524	41.57	10.56	52.13	73.00	-20.87	neutral	QP
7	6.139	35.85	10.72	46.57	60.00	-13.43	neutral	Average
8	6.139	45.74	10.72	56.46	73.00	-16.54	neutral	QP
9 PP	18.521	40.78	12.32	53.10	60.00	-6.90	neutral	Average
10 QP	18.521	45.21	12.32	57.53	73.00	-15.47	neutral	QP
11	20.910	35.56	12.63	48.19	60.00	-11.81	neutral	Average
12	20.910	42.19	12.63	54.82	73.00	-18.18	neutral	QP

Test Mode	Mode 3	Pol/Phase	Line1
Test Frequency	0.15 MHz ~ 30 MHz	Test Voltage	230Vac/50Hz
Test Date	Mar 18,2021	Test Engineer	David
Temperature	22 °C	Relative Humidity	67%

Note:

1. Emission Level = reading value + correction factor.
2. Correction factor = cable loss + insertion loss of LISN.
3. Q.P. is abbreviation of quasi-peak.
4. If the limit for the measurement with the average detector is met when using a receiver with a quasi-peak detector, the EUT shall be deemed to meet both limits.




	Read Freq	Read Level	Factor	Level	Limit Line	Over Limit	Pol/Phase	Remark	
	MHz	dBuV	dB	dBuV	dBuV	dB			
1	PP	0.185	54.23	10.22	64.45	66.00	-1.55	line1	Average
2	QP	0.185	55.96	10.22	66.18	79.00	-12.82	line1	QP
3		0.553	45.05	10.22	55.27	60.00	-4.73	line1	Average
4		0.553	49.13	10.22	59.35	73.00	-13.65	line1	QP
5		4.656	42.46	10.48	52.94	60.00	-7.06	line1	Average
6		4.656	48.28	10.48	58.76	73.00	-14.24	line1	QP
7		4.796	42.23	10.49	52.72	60.00	-7.28	line1	Average
8		4.796	47.62	10.49	58.11	73.00	-14.89	line1	QP
9		18.330	42.28	11.72	54.00	60.00	-6.00	line1	Average
10		18.330	47.26	11.72	58.98	73.00	-14.02	line1	QP
11		19.337	43.24	11.82	55.06	60.00	-4.94	line1	Average
12		19.337	47.52	11.82	59.34	73.00	-13.66	line1	QP

Test Mode	Mode 3	Pol/Phase	Neutral
Test Frequency	0.15 MHz ~ 30 MHz	Test Voltage	230Vac/50Hz
Test Date	Mar 18,2021	Test Engineer	David
Temperature	22 °C	Relative Humidity	67%

Note:

1. Emission Level = reading value + correction factor.
2. Correction factor = cable loss + insertion loss of LISN.
3. Q.P. is abbreviation of quasi-peak.
4. If the limit for the measurement with the average detector is met when using a receiver with a quasi-peak detector, the EUT shall be deemed to meet both limits.



	Read Freq	Read Level	Factor	Level	Limit Line	Over Limit	Pol/Phase	Remark	
	MHz	dBuV	dB	dBuV	dBuV	dB			
1	PP	0.185	54.15	10.23	64.38	66.00	-1.62	neutral	Average
2	QP	0.185	55.81	10.23	66.04	79.00	-12.96	neutral	QP
3		0.600	45.37	10.23	55.60	60.00	-4.40	neutral	Average
4		0.600	49.77	10.23	60.00	73.00	-13.00	neutral	QP
5		0.647	45.37	10.24	55.61	60.00	-4.39	neutral	Average
6		0.647	49.71	10.24	59.95	73.00	-13.05	neutral	QP
7		4.611	42.53	10.57	53.10	60.00	-6.90	neutral	Average
8		4.611	47.39	10.57	57.96	73.00	-15.04	neutral	QP
9		5.810	41.15	10.69	51.84	60.00	-8.16	neutral	Average
10		5.810	46.17	10.69	56.86	73.00	-16.14	neutral	QP
11		18.417	41.90	12.31	54.21	60.00	-5.79	neutral	Average
12		18.417	46.81	12.31	59.12	73.00	-13.88	neutral	QP

4. Radiated Emission Measurement

4.1 Limits for Emission Measurement

The EUT shall meet the limits of below Table when measured at the measuring distance R in accordance with the methods described in IEC 61000-6-4. If the reading on the measuring receiver shows fluctuations close to the limit, the reading shall be observed for at least 15 s at each measurement frequency; the highest reading shall be recorded, with the exception of any brief isolated high reading, which shall be ignored.

Required highest frequency for radiated measurement

Highest internal frequency (F_x)	Highest measured frequency
$F_x \leq 108$ MHz	1 GHz
$108 \text{ MHz} < F_x \leq 500$ MHz	2 GHz
$500 \text{ MHz} < F_x \leq 1$ GHz	5 GHz
$F_x > 1$ GHz	$5 \times F_x$ up to a maximum of 6 GHz
NOTE 1 Where the highest internal frequency is not known, tests are performed up to 6 GHz. NOTE 2 F_x is defined in 3.1.10.	

Where the F_x is unknown, the radiated emission measurements shall be performed up to 6 GHz.

Table 1 – Limits for radiated disturbance at a measuring distance of 10 m (dB(μ V/m))

Frequency range(MHz)	Limit
	Quasi-peak
30 to 230	40
230 to 1000	47
Note: Allowed measurement distances: 3 m, 5 m, 10 m or 30 m For equipment meeting the size criterion defined in 3.1.11, the measurements may be performed at the 3 m distance. Note this size criterion is currently under discussion.	

Where a different measurement distance is chosen, other than the reference distance defined in the limit column of Table 1, the limits shall be offset based upon the following formula:

$$\text{new limit} = \text{defined limit} - 20 \log (\text{measurement distance}/\text{reference distance})$$

The unit of metres shall be used for distance and dB(μ V/m) for the limits.

With regard to each table clause, the measurements shall be performed at only one distance.

Table 2 – Limits for radiated disturbance at a measuring distance of 3 m (dB (μV/m))

Frequency range (GHz)	Limit	
	Avg.	Peak
1 to 3	56	76
3 to 6	60	80

NOTE The lower limit applies at the transition frequency.


4.2 Test Procedures

Below 1GHz measurement


- a. The EUT was set up per the test configuration figured in the next section of this chapter to simulate the typical usage per the user's manual.
- b. If the EUT is tabletop equipment, it was placed on a rotatable table with a height of 0.8 meters above the reference ground plane and 3 meters away from the interference receiving antenna in the semi-anechoic chamber.
- c. If the EUT is floor-standing equipment, it was placed on a non-conducted support with a height up to 0.15 meters above the reference ground plane and 3 meters away from the interference-receiving antenna in the semi-anechoic chamber.
- d. Rapidly sweep the signal from 30MHz to 1GHz by using the spectrum through the Maximum-peak detector.
- e. Rotate the EUT from 0° to 360° and position the receiving antenna at heights from 1 to 4 meters above the reference ground plane continuously to determine at least three frequencies associated with higher emission levels and record them.
- f. Then measure each frequency found from step e. by using the spectrum with rotating the EUT and positioning the receiving antenna height to determine the maximum level.
- g. Finely tune the antenna and turntable around the recorded position of each frequency found from step f. by using the receiver through the Quasi-Peak detector per CISPR 16-1 to find out where the maximum level occurred.
- h. Record frequency, azimuth angle of the turntable, height, and polarization of the receiving antenna and compare the maximum level with the required limit.
- i. Change the receiving antenna to another polarization to measure radiated emission by following step d. to h. again.
- j. If the peak emission level measured from step e. is 4dB lower than the limit specified, then the emission values presented will be the peak value only. Otherwise, accurate Q.P. value will be measured and presented.

4.3 Test Configurations


Below 1GHz measurement



4.4 Photographs of the Test Configurations– Charge mode and stored energy mode



4.5 Photographs of the Test Configurations– PV mode




4.6 Test Results and data

Test Mode	Mode1	Pol/Phase	Vertical
Test Frequency	30 MHz ~ 1GHz	Test Voltage	230Vac/50Hz
Test Date	Mar 19,2021	Test Engineer	Dylan
Temperature	21 °C	Relative Humidity	43%

Note:

1. Emission Level = reading value + correction factor.
2. Correction factor = cable loss + antenna factor – gain of pre-amplifier.
3. Q.P is abbreviation of quasi-peak.




	Read Freq	Level	Factor	Limit Level	Over Limit	Pol/Phase	Remark
	MHz	dBuV	dB/m	dBuV/m	dBuV/m	dB	
1	30.043	49.65	-4.64	45.01	50.00	-4.99	vertical QP
2	39.299	56.99	-11.74	45.25	50.00	-4.75	vertical QP
3	55.805	56.36	-18.90	37.46	50.00	-12.54	vertical QP
4	86.807	54.82	-18.65	36.17	50.00	-13.83	vertical QP
5	319.937	47.24	-11.21	36.03	57.00	-20.97	vertical QP
6	400.432	44.04	-9.19	34.85	57.00	-22.15	vertical QP

Test Mode	Mode 1	Pol/Phase	Horizontal
Test Frequency	30 MHz ~ 1GHz	Test Voltage	230Vac/50Hz
Test Date	Mar 19,2021	Test Engineer	Dylan
Temperature	21 °C	Relative Humidity	43%

Note:

1. Emission Level = reading value + correction factor.
2. Correction factor = cable loss + antenna factor – gain of pre-amplifier.
3. Q.P is abbreviation of quasi-peak.




	Read Freq	Read Level	Factor	Limit Level	Over Limit	Pol/Phase	Remark
	MHz	dBuV	dB/m	dBuV/m	dBuV/m	dB	
1	30.531	41.05	-4.91	36.14	50.00	-13.86	horizontal QP
2	40.058	48.78	-12.51	36.27	50.00	-13.73	horizontal QP
3	56.593	53.37	-18.83	34.54	50.00	-15.46	horizontal QP
4	72.592	49.72	-17.97	31.75	50.00	-18.25	horizontal QP
5	319.937	48.20	-11.21	36.99	57.00	-20.01	horizontal QP
6	400.432	45.82	-9.19	36.63	57.00	-20.37	horizontal QP

Test Mode	Mode 2	Pol/Phase	Vertical
Test Frequency	30 MHz ~ 1GHz	Test Voltage	230Vac/50Hz
Test Date	Mar 19,2021	Test Engineer	Dylan
Temperature	21 °C	Relative Humidity	43%

Note:

1. Emission Level = reading value + correction factor.
2. Correction factor = cable loss + antenna factor – gain of pre-amplifier.
3. Q.P is abbreviation of quasi-peak.




	Read		Limit	Over			
Freq	Level	Factor	Level	Line	Limit	Pol/Phase	Remark
MHz	dBuV	dB/m	dBuV/m	dBuV/m	dB		
1	31.510	44.27	-5.57	38.70	50.00	-11.30	vertical QP
2	43.202	53.06	-14.74	38.32	50.00	-11.68	vertical QP
3	87.725	52.49	-18.59	33.90	50.00	-16.10	vertical QP
4	119.856	45.17	-11.98	33.19	50.00	-16.81	vertical QP
5	180.017	43.49	-14.49	29.00	50.00	-21.00	vertical QP
6	400.432	43.37	-9.19	34.18	57.00	-22.82	vertical QP

Test Mode	Mode 2	Pol/Phase	Horizontal
Test Frequency	30 MHz ~ 1GHz	Test Voltage	230Vac/50Hz
Test Date	Mar 19,2021	Test Engineer	Dylan
Temperature	21 °C	Relative Humidity	43%

Note:

1. Emission Level = reading value + correction factor.
2. Correction factor = cable loss + antenna factor – gain of pre-amplifier.
3. Q.P is abbreviation of quasi-peak.




	Read Freq	Level	Factor	Level	Limit	Over	Pol/Phase	Remark
	MHz	dBuV	dB/m	dBuV/m	dBuV/m	dB		
1	41.277	44.83	-13.40	31.43	50.00	-18.57	horizontal	QP
2	55.805	50.50	-18.90	31.60	50.00	-18.40	horizontal	QP
3	80.081	50.70	-18.49	32.21	50.00	-17.79	horizontal	QP
4	287.990	46.18	-11.94	34.24	57.00	-22.76	horizontal	QP
5	319.937	50.25	-11.21	39.04	57.00	-17.96	horizontal	QP
6	400.432	47.07	-9.19	37.88	57.00	-19.12	horizontal	QP

Test Mode	Mode 3	Pol/Phase	Vertical
Test Frequency	30 MHz ~ 1GHz	Test Voltage	230Vac/50Hz
Test Date	Mar 19,2021	Test Engineer	Dylan
Temperature	21 °C	Relative Humidity	43%

Note:

1. Emission Level = reading value + correction factor.
2. Correction factor = cable loss + antenna factor – gain of pre-amplifier.
3. Q.P is abbreviation of quasi-peak.




	Read Freq	Level	Factor	Level	Limit	Over	Pol/Phase	Remark
	MHz	dBuV	dB/m	dBuV/m	dBuV/m	dB		
1	30.253	46.37	-4.76	41.61	50.00	-8.39	vertical	QP
2	40.276	53.89	-12.68	41.21	50.00	-8.79	vertical	QP
3	58.819	58.15	-18.81	39.34	50.00	-10.66	vertical	QP
4	85.898	59.73	-18.71	41.02	50.00	-8.98	vertical	QP
5	159.784	49.18	-13.47	35.71	50.00	-14.29	vertical	QP
6	400.432	45.74	-9.19	36.55	57.00	-20.45	vertical	QP

Test Mode	Mode 3	Pol/Phase	Horizontal
Test Frequency	30 MHz ~ 1GHz	Test Voltage	230Vac/50Hz
Test Date	Mar 19,2021	Test Engineer	Dylan
Temperature	21 °C	Relative Humidity	43%

Note:

1. Emission Level = reading value + correction factor.
2. Correction factor = cable loss + antenna factor – gain of pre-amplifier.
3. Q.P is abbreviation of quasi-peak.



	Read Freq	Read Level	Factor	Level	Limit Line	Over Limit	Pol/Phase	Remark
	MHz	dBuV	dB/m	dBuV/m	dBuV/m	dB		
1	41.277	49.16	-13.40	35.76	50.00	-14.24	horizontal	QP
2	74.135	58.21	-18.12	40.09	50.00	-9.91	horizontal	QP
3	79.243	58.12	-18.40	39.72	50.00	-10.28	horizontal	QP
4	118.186	46.89	-12.17	34.72	50.00	-15.28	horizontal	QP
5	287.990	51.77	-11.94	39.83	57.00	-17.17	horizontal	QP
6	319.937	49.94	-11.21	38.73	57.00	-18.27	horizontal	QP

5. Harmonic Current Emission Measurement

5.1 Limits for Emission Measurement

Limits for Class A equipment	
Harmonics	Max. Permissible
Order	Harmonics current
n	A
Odd harmonics	
3	2.30
5	1.14
7	0.77
9	0.40
11	0.33
13	0.21
15<=n<=39	0.15×15/n
Even harmonics	
2	1.08
4	0.43
6	0.30
8<=n<=40	0.23×8/n

Limits for Class D equipment		
Harmonics	Max. Permissible	Max. Permissible
Order	Harmonics current per	Harmonics current
n	Watt mA/W	A
Odd Harmonics only		
3	3.4	2.30
5	1.9	1.14
7	1.0	0.77
9	0.5	0.40
11	0.35	0.33
13	0.30	0.21
15<=n<=39	3.85/n	0.15 x15/n

NOTE:

- Class A and Class D are classified according to item section 5 of EN IEC 61000-3-2:2019.
- According to EN IEC 61000-3-2:2019, the above limits for all equipment except for lighting equipment are for all applications having an active input power > 75 W and no limits apply for equipment with an active input power up to and including 75 W.

Test requirement :

The repeatability of the average value for the individual harmonic currents over the entire test observation period shall be better than $\pm 5\%$ of the applicable limit, when the following conditions are met:

- the same equipment under test (EUT) (not another of the same type, however similar);
- identical test conditions;
- the same test system;
- identical climatic conditions, if relevant.

NOTE

This repeatability requirement serves the purpose of defining the necessary observation period, see 6.2.4. It is not intended to serve as a pass/fail criterion for the assessment of compliance with the requirements of this standard.

5.2 Test Procedures

- a. The EUT was set up per the test configuration figured in the next section of this chapter to simulate the typical usage per the user's manual.
- b. If the EUT is tabletop equipment, it was placed on a wooden table with a height of 0.8 meters in the shielded room.
- c. If the EUT is floor-standing equipment, it was placed on a non-conducted support with a height of 0.1 meters in the shielded room.
- d. Decide the classification of the EUT as following:

Class A : - balanced three-phase equipment

- household appliances, excluding equipment identified as class D
- tools, excluding portable tools
- dimmers for incandescent lamps
- audio equipment
- equipments not specified in one of the three other classes

Class B : - portable tools

- arc welding equipment which is not professional equipment.


Class C : - lighting equipment

Class D : - Equipment specified power less than or equal to 600W of the following types:

- personal computers and personal computer monitors
- television receivers
- refrigerators and freezers having one or more variable-speed drives to control compressor motor(s).

- e. Connects the EUT's power source to the mains power supplied by the test instrument. Turn on the EUT.
- f. Operating the EUT as required and measuring the harmonic current emissions on the current carrying lines of EUT's power source.

5.3 Test Configurations



5.4 Photographs of the Test Configurations



5.5 Test Results and data

Test Mode	Mode1	Final Test Result	Pass
Basic Standard	IEC61000-3-2	Test Voltage	230Vac/50Hz
Test Date	Mar 19,2021	Test Engineer	David
Temperature	23 °C	Relative Humidity	62%
Test frequency	50Hz	Test time	3 minutes
Max watts	3.626kW	Ref. Max Current	16.014A
Classification	Class A	Rsce	

Test information			
	Average	Peak	Limit
THC	423.972mA	480.434mA	N/A
POHC	88.385mA	93.585mA	307.866mA
Voltage Crest Factor	1.409	1.411	N/A
Current Crest Factor	1.474	1.53	N/A

Harmonic results							
Harmonic	Status	Avg (A)	Avg L(A)	Avg %ofL	Peak (A)	Peak L(A)	Peak %ofL
1	PASS	15.959	No Limit	N/A	16.014	No Limit	N/A
2	PASS	0.27397	1.08	25.3676	0.31566	1.62	19.4852
3	PASS	0.21462	2.3	9.3313	0.2472	3.45	7.16522
4	PASS	0.18437	0.43	42.8767	0.2014	0.645	31.2248
5	PASS	0.16766	1.14	14.707	0.19043	1.71	11.1363
6	PASS	0.10614	0.3	35.38	0.11994	0.45	26.6533
7	PASS	0.099074	0.77	12.8668	0.11281	1.155	9.7671
8	PASS	0.081218	0.23	35.3122	0.097136	0.345	28.1554
9	PASS	0.086919	0.4	21.7298	0.098052	0.6	16.342
10	PASS	0.061105	0.184	33.2092	0.079675	0.276	28.8678
11	PASS	0.097106	0.33	29.4261	0.11276	0.495	22.7798
12	PASS	0.054893	0.15333	35.8006	0.070162	0.229995	30.5059
13	PASS	0.060597	0.21	28.8557	0.075142	0.315	23.8546
14	PASS	0.06416	0.13143	48.8169	0.080542	0.197145	40.8542
15	PASS	0.083186	0.15	55.4573	0.10113	0.225	44.9467

Test Mode	Mode1	Final Test Result	Pass
Basic Standard	IEC61000-3-2	Test Voltage	230Vac/50Hz
Test Date	Mar 19,2021	Test Engineer	David
Temperature	23 °C	Relative Humidity	62%
Test frequency	50Hz	Test time	3 minutes
Max watts	3.626kW	Ref. Max Current	16.014A
Classification	Class A	Rsce	

Harmonic results							
Harmonic	Status	Avg (A)	Avg L(A)	Avg %ofL	Peak (A)	Peak L(A)	Peak %ofL
16	PASS	0.067672	0.115	58.8452	0.081935	0.1725	47.4986
17	PASS	0.061317	0.13235	46.3294	0.078142	0.198525	39.3613
18	PASS	0.064826	0.10222	63.4181	0.074392	0.15333	48.5176
19	PASS	0.050622	0.11842	42.7478	0.062871	0.17763	35.3944
20	PASS	0.045014	0.095612	47.0799	0.056173	0.143418	39.1673
21	PASS	0.037537	0.10714	35.0355	0.044061	0.16071	27.4165
22	PASS	0.039357	0.095612	41.1632	0.044393	0.143418	30.9536
23	PASS	0.051944	0.097826	53.0984	0.056066	0.146739	38.208
24	PASS	0.032522	0.095612	34.0146	0.036718	0.143418	25.6021
25	PASS	0.027639	0.095612	28.9075	0.031706	0.143418	22.1074
26	PASS	0.02754	0.095612	28.8039	0.032841	0.143418	22.8988
27	PASS	0.026333	0.095612	27.5415	0.029992	0.143418	20.9123
28	PASS	0.024912	0.095612	26.0553	0.029791	0.143418	20.7721
29	PASS	0.025089	0.095612	26.2404	0.02917	0.143418	20.3391
30	PASS	0.020853	0.095612	21.81	0.024026	0.143418	16.7524
31	PASS	0.020032	0.095612	20.9513	0.022703	0.143418	15.83
32	PASS	0.019166	0.095612	20.0456	0.022434	0.143418	15.6424
33	PASS	0.020437	0.095612	21.3749	0.02367	0.143418	16.5042
34	PASS	0.018066	0.095612	18.8951	0.021093	0.143418	14.7074
35	PASS	0.016987	0.095612	17.7666	0.019068	0.143418	13.2954
36	PASS	0.015888	0.095612	16.6172	0.018569	0.143418	12.9475
37	PASS	0.015922	0.095612	16.6527	0.018496	0.143418	12.8966
38	PASS	0.014166	0.095612	14.8161	0.016846	0.143418	11.7461
39	PASS	0.015572	0.095612	16.2867	0.018324	0.143418	12.7766
40	PASS	0.014836	0.095612	15.5169	0.017386	0.143418	12.1226

6. Voltage Fluctuations and Flickers Emission Measurement


6.1 Limits for Emission Measurement

- the short-term flicker indicator, P_{st} , shall not be greater than 1.0;
- the long-term flicker indicator, P_{lt} , shall not be greater than 0.65;
- the relative steady-state voltage change, d_c , shall not exceed 3.3%;
- the voltage change with time, $d(t)$, during a voltage change shall not exceed 3.3% for more than 500ms.
- the maximum relative voltage change, d_{max} , shall not exceed
 - a) 4% without additional conditions;
 - b) 6% for equipment which is switched manually
 - c) 7% for equipment which is attended whilst in use


6.2 Test Procedures

- a. The EUT was set up per the test configuration figured in the next section of this chapter to simulate the typical usage per the user's manual.
- b. If the EUT is tabletop equipment, it was placed on a wooden table with a height of 0.8 meters in the shielded room.
- c. If the EUT is floor-standing equipment, it was placed on a non-conducted support with a height of 0.1 meters in the shielded room.
- d. Decide the type of EUT to define the d_{max} limit and its corresponding test methods described in the relative standard.
- e. Maintain the supply voltage to be $\pm 2\%$ of the EUT's rated voltage and also the frequency to be $50\text{Hz} \pm 0.5\%$.
- f. Connects the EUT's power source to the mains power supplied by the test instrument.
- g. Operating the EUT as required and measuring the voltage fluctuation and flicker of EUT's power source.
- h. Verify the fluctuations of the test supply voltage to be less than 0.4 before and after the test.

6.3 Test Configurations



6.4 Photographs of the Test Configurations



6.5 Test Results and data

Test Mode	Mode1	Final Test Result	Pass
Basic Standard	IEC61000-3-3	Test Voltage	230V/50Hz
Test Date	Mar 19,2021	Test Engineer	David
Temperature	23 °C	Relative Humidity	62%
Test frequency	50Hz	PST Test time	10 minutes
Class	Voltage	Mode	Normal (4%)
PLT	1 PSTs		

Limitation	DC (%)	Dmax (%)	Tmax (s)	PST	PLT	
	4	3.3	0.5	10 minutes	1 PSTs	
Test results						
PST no.	Status	DC (%)	Dmax (%)	Tmax (s)	PST	PLT
1	Pass	0.36769	0.51450	0.00000	0.15738	0.15738

7. Electrostatic Discharge (ESD) Immunity Test

7.1 Specifications of Immunity Test Requirement

- a. In the case of air discharge testing the climatic conditions shall be within the following ranges:
 - ambient temperature: 15°C to 35°C;
 - relative humidity : 30% to 60%;
 - atmospheric pressure : 86 KPa (860 mbar) to 106 KPa (1060 mbar).
- b. Test programs and software shall be chosen so as to exercise all normal modes of operation of the EUT. The use of special exercising software is encouraged, but permitted only where it can be shown that the EUT is being comprehensively exercised.
- c. The test voltage shall be increased from the minimum to the selected test severity level, in order to determine any threshold of failure. The final severity level should not exceed the product specification value in order to avoid damage to the equipment.
- d. The test shall be performed with both air discharge and contact discharge. On reselected points at least 10 single discharges (in the most sensitive polarity) shall be applied on air discharge. On reselected points at least 10 single discharges (in the most sensitive polarity) shall be applied on contact discharge.
- e. For the time interval between successive single discharges an initial value of one second is recommended. Longer intervals may be necessary to determine whether a system failure has occurred.
- f. In the case of contact discharges, the tip of the discharge electrode shall touch the EUT before the discharge switch is operated.
- g. In the case of painted surface covering a conducting substrate, the following procedure shall be adopted :
 - If the coating is not declared to be an insulating coating by the equipment manufacturer, then the pointed tip of the generator shall penetrate the coating so as to make contact with the conducting substrate.
 - Coating declared as insulating by the manufacturer shall only be submitted to the air discharge.
 - The contact discharge test shall not be applied to such surfaces.
- h. In the case of air discharges, the round discharge tip of the discharge electrode shall be approached as fast as possible (without causing mechanical damage) to touch the EUT . After each discharge, the ESD generator (discharge electrode) shall be removed from the EUT. The generator is then retriggered for a new single discharge. This procedure shall be repeated until the discharges are completed. In the case of an air discharge test, the discharge switch, which is used for contact discharge, shall be closed.

7.2 Test Severity Levels


Contact Discharge		Air Discharge	
Level	Test Voltage (KV) of Contact discharge	Level	Test Voltage (KV) of Air Discharge
1	±2	1	±2
2	±4	2	±4
3	±6	3	±8
4	±8	4	±15
X	Specified	X	Specified
Remark: "X" is an open level.			

7.3 Test Procedures


- a. The EUT was set up per the test configuration figured in the next section of this chapter to simulate the typical usage per the user's manual.
- b. If the EUT is tabletop equipment, it was placed on a wooden table with a height of 0.8 meters above the ground reference plane in the shielded room. Also a HCP (Horizontal Coupling Plane) which was connected to the ground reference plane via a cable with a 470k Ω resistor located at each end was placed on the wooden table and isolated with the EUT by an insulating support 0.5mm thick. The ground reference plane shall project beyond the EUT or HCP by at least 0.5m on all sides.
- c. If the EUT is floor-standing equipment, it was placed on a non-conducted support with a height of 0.1 meters above the ground reference plane in the shielded room. The ground reference plane shall project beyond the EUT by at least 0.5m on all sides.
- d. Keep the EUT 1m away from all other metallic walls in the shielded room as the minimum distance.
- e. The static electricity discharges shall be applied only to those points and surfaces of the EUT which are accessible to persons during normal use. Contact discharge is the preferred test method and it is applied to the conductive surfaces of EUT and coupling planes. Air discharge shall be used where contact discharge cannot be performed and it is applied to the insulating surfaces of EUT.
- f. The discharge return cable of the generator shall be kept at a distance of at least 0.2m from the EUT whilst the discharge is being applied.
- g. The time interval between successive single discharges was at least 1 second.
- h. Select appropriate points of the EUT for contact discharge and put marks on it to indicate the tested point(s). Then start the contact discharge with the tip of the discharge electrode to touch the EUT before the discharge switch is operated.
- i. Use the round discharge tip of the discharge electrode to scan the EUT to select the points for air discharge. Then start the air discharge by approaching the discharge electrode as fast as possible to touch the EUT. After each discharge, the ESD generator shall be removed from the EUT.
- j. The indirect HCP discharge test is applied at the front edge of each HCP opposite the center point of each unit of the EUT and 0.1m from the front of the EUT. The long axis of the discharge electrode shall be in the plane of the HCP and perpendicular to its front edge during the discharge.

- k. The indirect VCP (Vertical Coupling Plane) discharge test is applied to the center of one vertical edge of the coupling plane. The VCP, of dimensions 0.5m×0.5m, is placed parallel to, and positioned at a distance of 0.1m from the EUT. It shall be applied with sufficient different positions such that the four faces of the EUT are completely illuminated.

7.4 Test Configurations



7.5 Photographs of the Test Configurations



7.6 Test Results

Test Mode	Mode 1	Final Test Result	Pass
Test Date	Mar 19,2021	Test Engineer	David
Temperature	23 °C	Relative Humidity	56 %
Atmospheric Pressure	1005 hPa		

Pass performance criteria	A
Required performance criteria	B
Basic Standard	IEC 61000-4-2
Product Standard	IEC 61000-6-2
Test Voltage	±2 / ±4 / ±8 KV for air discharge, ±4 KV for contact discharge

		Contact Discharge							
		10 times / each							
		2 KV		4 KV		6 KV		8 KV	
Voltage		+	-	+	-	+	-	+	-
No\ Point\ Polarity		+	-	+	-	+	-	+	-
	HCP Right	---	---	A	A	---	---	---	---
	HCP Left	---	---	A	A	---	---	---	---
	HCP Rear	---	---	A	A	---	---	---	---
	HCP Front	---	---	A	A	---	---	---	---
	VCP Right	---	---	A	A	---	---	---	---
	VCP Left	---	---	A	A	---	---	---	---
	VCP Rear	---	---	A	A	---	---	---	---
	VCP Front	---	---	A	A	---	---	---	---
A	Screw	---	---	A	A	---	---	---	---
B	RJ45 shield	---	---	A	A	---	---	---	---
C	GND screw	---	---	A	A	---	---	---	---
D	Fuse holder	---	---	A	A	---	---	---	---

Note: "A" means the EUT function is normal working during the test.


		AIR Discharge							
		10 times / each							
Voltage		2 KV		4 KV		8 KV		15 KV	
No\Point\Polarity		+	-	+	-	+	-	+	-
1	Enclosure	A	A	A	A	A	A	---	---
2	Screen edge	A	A	A	A	A	A	---	---
3	Switch	A	A	A	A	A	A	---	---
4	USB port	A	A	A	A	A	A	---	---
5	AC input	A	A	A	A	A	A	---	---
6	AC output	A	A	A	A	A	A	---	---
7	DC output	A	A	A	A	A	A	---	---
8	Vents	A	A	A	A	A	A	---	---


Note: "A" means the EUT function is normal working during the test.


Observation of Performance during Test

(1) Normal operation condition specified by manufacturer during the test.

7.7 Photographs of the Test Points on the EUT for ESD Test







8. Radiated Electromagnetic Field (RS) Immunity Test

8.1 Test Requirement

- a. The equipment to be tested is placed in the center of the enclosure on a wooden table. The equipment is then connected to power and signal leads according to pertinent installation instructions.
- b. The antenna which is enabling the complete frequency range of 80-1000 MHz is placed 2m away from the equipment. The required field strength is determined by placing the field strength meter(s) on top of or directly alongside the equipment under test and monitoring the field strength meter via a remote field strength indicator outside the enclosure while adjusting the continuous-wave to the applicable antennae.
- c. The test is normally performed with the antenna facing the most sensitive side of the EUT. The polarization of the field generated by the bucolical antenna necessitates testing each position twice, once with the antenna positioned vertically and again with the antenna positioned horizontally. The circular polarization of the field from the log-spiral antenna makes a change of position of the antenna unnecessary.
- d. At each of the above conditions, the frequency range is swept 80-1000 MHz, pausing to adjust the R.F. signal level or to switch oscillators and antenna. The rate of sweep is in the order of $1.5 \cdot 10^{-3}$ decades/s. The sensitive frequencies or frequencies of dominant interest may be discretely analyzed.


8.2 Test Severity Level

Frequency Band : 80-6000 MHz	
Level	Test field strength (V/m)
1	1
2	3
3	10
X	Specified
Remark: "X" is an open class.	


8.3 Test Procedures

- a. The EUT was set up per the test configuration figured in the next section of this chapter to simulate the typical usage per the user's manual.
- b. If the EUT is tabletop equipment, it was placed on a wooden table with a height of 0.8 meters and 2 meters away from the transmitting antenna in the fully anechoic chamber.
- c. If the EUT is floor-standing equipment, it was placed on a non-conducted support with a height of 0.1 meters and 2 meters away from the transmitting antenna in the fully anechoic chamber. Also if the floor-standing equipment which is capable of being stood on a non-conducting 0.8m high platform may be so arranged.
- d. All EUT's individual faces shall be fully enclosed by the "uniform area" and its wires shall be arranged parallel to the uniform area of the field.
- e. Before testing the EUT, the intensity of the established field strength is checked by placing the field sensor at a calibration grid point to give the calibrated field strength to measure the EUT.
- f. After the calibration has been verified, the test field can be generated using the values obtained from the calibration.
- g. Perform the test with the specified immunity level in the test frequency range and with the specified modulation type.
- h. The transmitting antenna is normally facing each of the four sides of the EUT with two polarizations (Vertical and Horizontal) to perform the test.
- i. The dwell time at each frequency shall be not less than the time necessary for the EUT to be exercised and be able to respond.
- j. The sensitive frequencies of EUT shall be analyzed separately, if any.
- k. Record the performance of the EUT.

8.4 Test Configurations



8.5 Photographs of the Test configurations



8.6 Test Result and Data

Test Mode	Mode 1	Final Test Result	Pass
Test Date	Mar 19,2021	Test Engineer	Dylan
Temperature	25°C	Relative Humidity	50 %
Atmospheric Pressure	1006 hPa		

Pass performance criteria	A
Required performance criteria	A
Basic Standard	IEC 61000-4-3
Product Standard	IEC 61000-6-2
Frequency Range	80~1000 MHz, 1400M-6000MHz
Modulation	80% AM1kHz modulation
Dwell time	3 S
Frequency Step Size	1 %

Frequency (MHz)	Antenna Polarization	Face	Field strength (V/m)	Result
80~1000	Vertical	Front	10	A
80~1000	Vertical	Rear	10	A
80~1000	Vertical	Left	10	A
80~1000	Vertical	Right	10	A
80~1000	Horizontal	Front	10	A
80~1000	Horizontal	Rear	10	A
80~1000	Horizontal	Left	10	A
80~1000	Horizontal	Right	10	A

Note: "A" means the EUT function is normal working during the test.

Frequency (MHz)	Antenna Polarization	Face	Field strength (V/m)	Result
1400-6000	Vertical	Front	3	A
1400-6000	Vertical	Rear	3	A
1400-6000	Vertical	Left	3	A
1400-6000	Vertical	Right	3	A
1400-6000	Horizontal	Front	3	A
1400-6000	Horizontal	Rear	3	A
1400-6000	Horizontal	Left	3	A
1400-6000	Horizontal	Right	3	A

Observation of Performance during Test

(1) Normal operation condition specified by manufacturer during the test.

9. Electrical fast transient / burst (EFT) Immunity Test

9.1 Test Procedure

- a. The EUT was set up per the test configuration figured in the next section of this chapter to simulate the typical usage per the user's manual.
- b. If the EUT is tabletop equipment, it was placed on a non-conducted support with a height 0.1 meters above the ground reference plane. Also the ground reference plane is placed on a wooden table with a height of 0.8 meters in the shielded room. The ground reference plane shall project beyond the EUT by at least 0.1m on all sides.
- c. If the EUT is floor-standing equipment, it was placed on a non-conducted support with a height of 0.1 meters above the ground reference plane in the shielded room. The ground reference plane shall project beyond the EUT by at least 0.1m on all sides.
- d. The test generator and the coupling/decoupling network shall be placed directly on, and bonded to, the ground reference plane.
- e. All cables to the EUT shall be placed on the insulation support 0.1 m above the ground reference plane. Cables not subject to electrical fast transients shall be routed as far as possible from the cable under test to minimize the coupling between the cables.
- f. Keep the EUT 0.5m away from all other conductive structures, except the ground reference plane beneath the EUT as the minimum distance. Also if any, the minimum distance between the coupling clamp and all other conductive structures, except the ground reference plane beneath the coupling clamp and EUT shall be 0.5m.
- g. Keep the length of the power and signal lines, if required, between the coupling device and the EUT to be 0.5m. If a non-detachable supply cable more than 0.5m long, the excess length of this cable shall be folded to avoid a flat coil and situated at a distance of 0,1 m above the ground reference plane.
- h. Connect the EUT's power source to the appropriate power through the coupling devices and perform the specified test level.
- i. If any, connect all the I/O signal, data and control lines between EUT and accessories/support units through the coupling devices and perform the specified test level.
- j. Record the performance of the EUT.

9.2 Test Severity Levels


The following test severity levels are recommended for the fast transient/burst test :

Open circuit output test voltage $\pm 10\%$		
Level	On Power Supply	On I/O signal, data and control line
1	0.5 KV	0.25 KV
2	1.0 KV	0.50 KV
3	2.0 KV	1.00 KV
4	4.0 KV	2.00 KV
X	Specified	Specified


Remark : " X " is an open level. The level is subject to negotiation between the user and manufacturer or is specified by the manufacturer.

9.3 Test Configurations

Power supply port Test



I/O signal, data and control port Test (if any)



9.4 Photographs of the Test Configurations



9.5 Test Result and Data

Test Mode	Mode1	Final Test Result	Pass
Test Date	Mar 19,2021	Test Engineer	David
Temperature	23 °C	Relative Humidity	56 %
Atmospheric Pressure	1005 hPa		

Pass performance criteria	A
Required performance criteria	B
Basic Standard	IEC 61000-4-4
Product Standard	IEC 61000-6-2
Test Voltage	On AC input power port ± 2.0 KV On AC output power port -
Pulse	5/50 ns
Burst	15m/300ms
Repetition Rate	5 kHz
Test time	1 min/each condition

Phase	For AC input power port					
	1kV		2 kV		kV	
	+	-	+	-	+	-
L1	-	-	A	A		
N	-	-	A	A		
PE	-	-	A	A		
L1-N	-	-	A	A		
L1-PE	-	-	A	A		
N-PE	-	-	A	A		
L1-N-PE	-	-	A	A		

Note: "A" means the EUT function is normal working during the test.

Observation of Performance during Test

(1) Normal operation condition specified by manufacturer during the test.

10. Surge Immunity Test

10.1 Test Procedure

- a. The EUT was set up per the test configuration figured in the next section of this chapter to simulate the typical usage per the user's manual.
- b. If the EUT is tabletop equipment, it was placed on a wooden table with a height of 0.8 meters in the shielded room.
- c. If the EUT is floor-standing equipment, it was placed on a non-conducted support with a height of 0.1 meters above the ground reference plane in the shielded room.
- d. For the surge test applied to EUT's power supply and unshielded unsymmetrical interconnection lines, if required, the capacitive coupling network are used.
- e. If any, the surge test applied to the unshielded symmetrically interconnection lines of EUT, the gas arrestors coupling network are used.
- f. Keep the interconnection line, if required, or power cord between the EUT or its power source and the coupling / decoupling network to be 2m in length (or shorter).
- g. The surges have to be applied synchronized to the voltage phase at the zero-crossing and the peak value of the a.c. voltage wave (positive and negative).
- h. All lower levels including the selected test level shall be satisfied and the test voltage has to be increased by steps up to the specified test level.
- i. Connect the EUT's power source to the appropriate power through the coupling devices and perform the specified test level.
- j. If any, connect all the interconnection lines between EUT and accessories/support units through the coupling devices and perform the specified test level.
- k. Record the performance of the EUT.


10.2 Test Severity Level

Level	Open-circuit test voltage (kV)	
	Line-to-line	Line-to-ground ^b
1	---	0.5
2	0.5	1.0
3	1.0	2.0
4	2.0	4.0
X ^a	Special	Special


^a "X" and be any level, above, below or in between the others. The level shall be specified in the dedicated equipment specification.

^b For symmetrical interconnection lines the test can be applied to multiple lines simultaneously with respect to ground, i.e. "lines to ground".

10.3 Test Configurations



10.4 Photographs of the Test Configurations



10.5 Test Result and Data

Test Mode	Mode 1	Final Test Result	Pass
Test Date	Mar 19,2021	Test Engineer	David
Temperature	23°C	Relative Humidity	56%
Atmospheric Pressure	1005 hPa		

Pass performance criteria	A
Required performance criteria	B
Basic Standard	IEC 61000-4-5
Product Standard	IEC 61000-6-2
Test Voltage	On AC input power port --± 0.5 kV, ± 1.0 kV On AC output power port --± 0.5 kV, ± 1.0 kV, ± 2.0 kV
Waveform	On Power Supply --1.2/50µs(8/20µs)
Repetition rate	60 sec
Test time	5 time/each condition

For AC input power port						
Voltage	Phase	Polarity	0°	90°	180°	270°
0.5kV, 1kV	L1-N	+	A	A	A	A
		-	A	A	A	A
0.5kV, 1kV,2kV	L1-PE	+	A	A	A	A
		-	A	A	A	A
0.5kV, 1kV,2kV	N-PE	+	A	A	A	A
		-	A	A	A	A

Note: "A" means the EUT function is normal working during the test.

"B" means the following description:

Observation of Performance during Test

- (1) Normal operation condition specified by manufacturer during the test.

11. Conducted disturbances (CS) Immunity Test

11.1 Test Procedure


- a. The EUT was set up per the test configuration figured in the next section of this chapter to simulate the typical usage per the user's manual.
- b. If the EUT is tabletop equipment, it was placed on a non-conducted support with a height 0.1 meters above the ground reference plane. Also the ground reference plane is placed on a wooden table with a height of 0.8 meters in the shielded room.
- c. If the EUT is floor-standing equipment, it was placed on a non-conducted support with a height of 0.1 meters above the ground reference plane in the shielded room.
- d. Decide the injection methods and test points according to the relative standard.
- e. All relevant cables shall be provide with the appropriate coupling and decoupling devices at a distance between 0.1m and 0.3m from the projected geometry of the EUT on the ground reference plane.
- f. All cables connected to each Auxiliary Equipment (AE), other than those being connected to the EUT, shall not be bundled nor wrapped and shall be kept between 30mm and 50mm above the ground reference plane.
- g. The test shall be performed with the test generator connected to each of the coupling and decoupling devices in turn while the other non-excited RF input ports of the coupling devices are terminated by a 50 load resistor.
- h. Perform the test with the specified immunity level inthe test frequency range and with the specified modulation type.
- i. The dwell time at each frequency shall be not less than the time necessary for the EUT to be exercised and be able to respond.
- j. The sensitive frequencies of EUT and harmonics or frequencies of dominant interest shall be analyzed separately, if any.
- k. Record the performance of the EUT.

11.2 Test Severity Levels


Level	Voltage Level (e.m.f.)
1	1 V
2	3 V
3	10 V
x	Specified
NOTE - x is an open class. This level can be specified in the product specification.	

11.3 Test Configurations

Power supply and LAN port Test



I/O signal, data and control port Test (if any)



11.4 Photographs of the Test Configurations



11.5 Test Result and Data

Test Mode	Mode1	Final Test Result	Pass
Test Date	Mar 19,2021	Test Engineer	Dylan
Temperature	25°C	Relative Humidity	50%
Atmospheric Pressure	1006 hPa		

Pass performance criteria	A
Required performance criteria	A
Basic Standard	IEC 61000-4-6
Product Standard	IEC 61000-6-2
Frequency Range	0.15~-80MHz
Modulation	AM 80% , 1KHz sine wave
Dwell time	3 S
Frequency Step Size	1 %
Coupling mode	CDN

For AC input power port			
Frequency	Test Mode	Voltage(V)	Result
0.15 ~ 80MHz	Power(M3)	10	A

Observation of Performance during Test

(1) Normal operation condition specified by manufacturer during the test.

12. Power frequency magnetic field (PFM) Immunity Test


12.1 Test Procedure

- a. The EUT was set up per the test configuration figured in the next section of this chapter to simulate the typical usage per the user's manual.
- b. If the EUT is tabletop equipment, it was placed on a wooden table with a height 0.8 meters.
- c. If the EUT is floor-standing equipment, it was placed on a non-conducted support with a height of 0.1 meters above the ground reference plane (minimum size is 1m 1m) in the shielded room.
- d. For the tabletop equipment, the induction coil with a square form in 1m side (or diameter) is used and shall enclose the EUT placed at its center. For the floor-standing equipment, the induction coil shall be able to envelop the EUT and made of conductors of relatively small cross-section.
- e. The dimensions of induction coil shall be able to keep the magnetic fields over the whole volume of the EUT with an acceptable variation of $\pm 3\text{dB}$.
- f. The test generator shall be placed at less than 3m distance from the induction coil.
- g. Keep all cables of EUT to be exposed to the magnetic field for 1m of their length.
- h. Before the test, maintain the electromagnetic field value of the test environment to be at least 20dB lower than the selected test level. Then tune up the currents of the test generator and use the Gauss Meter to calibrate the specified test level at the center of the induction coil.
- i. Perform the test with the specified magnetic field by rotating the induction coil to three different orientations to generate X, Y and Z directed magnetic field sequentially.
- j. Record the performance of the EUT.


12.2 Test Severity Levels

Level	Magnetic field strength (A/m)
1	1
2	3
3	10
4	30
5	100
X ¹⁾	special
NOTE 1 "X" is an open level. This level can be given in the product specification.	

12.3 Test Configurations



12.4 Photographs of the Test Configurations



12.5 Test Result and Data

Test Mode	Mode 1	Final Test Result	Pass
Test Date	Mar 19,2021	Test Engineer	David
Temperature	22°C	Relative Humidity	60%
Atmospheric Pressure	1006 hPa		

Pass performance criteria	A
Required performance criteria	A
Basic Standard	IEC 61000-4-8
Product Standard	IEC 61000-6-2
Power FrequencyMagnetic Field	<u>50</u> Hz, <u>30</u> A/m

Coil Orientation	Testing duration	Results
X-axis	1.0 Min	A
Y-axis	1.0 Min	A
Z-axis	1.0 Min	A

Note:“A” Mean the EUT function is normal working during the test.

Observation of Performance during Test

(1) Normal operation condition specified by manufacturer during the test.

13. Voltage Dips and Voltage Interruptions Immunity

13.1 Test procedure


- a. The EUT was set up per the test configuration figured in the next section of this chapter to simulate the typical usage per the user's manual.
- b. If the EUT is tabletop equipment, it was placed on a wooden table with a height 0.8 meters above the ground reference plane in the shielded room.
- c. If the EUT is floor-standing equipment, it was placed on a non-conducted support with a height of 0.1 meters above the ground reference plane in the shielded room.
- d. The test shall be performed with the EUT connected to the test Generator with the shortest power supply cable as specified by the manufacturer.
- e. If any, tests on the three-phase EUT are accomplished by using three sets of equipment mutually synchronized.
- f. During the tests, the main voltage for testing is monitored within an accuracy of 2% and the zero crossing control of the generators must have an accuracy of $\pm 10^\circ$.
- g. The EUT shall be tested for each selected combination of test level and duration with a sequence of three dips/interruptions with intervals of 10 sec. minimum (between each test event). Each representative mode of operation shall be test.
- h. Abrupt changes in supply voltage shall occur at zero crossings of the voltage and additional angles preferably selected from 0° , 45° , 90° , 135° , 180° , 225° , 270° , 315° on each phase.
- i. Connect the EUT's power source to the appropriate power through the test generator and perform the specified test level.
- j. Record the performance of the EUT.

13.2 Test severity

- a. Source voltage and frequency : AC 230V / 50Hz, Single phase.
- b. Test of interval : 10 sec.
- c. Level and duration : Sequence of 3 dips/interrupts.

Voltage dips and Interrupt reduction (%)	Test Duration (period)	Required performance criteria
>95%	250	C
30%	25	C
60%	10	C
>95%	1	B

13.3 Test Configurations



13.4 Photographs of the Test Configurations



13.5 Test Result and data

Test Mode	Mode 1	Final Test Result	Pass
Test Date	Mar 19,2021	Test Engineer	David
Temperature	23°C	Relative Humidity	62%
Atmospheric Pressure	1006 hPa		

Pass performance criteria	Afor voltage interruption, A/A/A for voltage dips
Required performance criteria	C for voltage interruption, C/C/B for voltage dips
Basic Standard	IEC 61000-4-34
Product Standard	IEC 61000-6-2

Voltage(UT): AC <u>230V</u> <u>50</u> Hz Interval(s) : <u>10s</u> Times : <u>3</u>			
Test mode	Test level reduction %	Durations (period)	Result
Voltage interruptions	>95%	250	A
Voltage dips	30%	25	A
	60%	10	A
	>95%	1	A

Note:“A” Mean the EUT function is normal working during the test.

The EUT has DC battery backup system, so the working status would follow manufacturer specification to definition.

Observation of Performance during Test

- (1) Normal operation condition specified by manufacturer during the test.
- (2) In 0% 1cycle amd 0% 250 cycles test, the output is changed from AC output mode to battery mode. When the disturbance stops, it will automatically recover, but the lamp load status is keep, so the judgment is A

14. List of Measuring Equipment

Conducted Emission					
Instrument	Manufacturer	Model No.	Serial No.	Calibration Date	Valid Date
EMI test receiver	R&S	ESR7	102004	5/11/2020	5/10/2021
Receiver	R&S	ESHS10	835499/012	10/30/2020	10/29/2021
LISN	INTRX	LIN63-4	1803001	3/9/2021	3/8/2022
Coaxial Cable	SUHNER	RG214	C001-1358175	07/16/2020	07/15/2021
Attenuator	JYEBAO	FAT-NM5NF5T6G2W10	ATT002	9/24/2020	9/23/2021
Attenuator	JYEBAO	FAT-BM5BF5T3G2W10	ATT004	1/15/2021	1/14/2022
test software	Audix	E3	20180316b	NA	NA

Radiated Emission below 1GHz					
Instrument	Manufacturer	Model No.	Serial No.	Calibration Date	Valid Date
EMI test receiver	R&S	ESR7	102004	5/11/2020	5/10/2021
Loop antenna	SCHWARZBECK	FMZB 1519B	00013	4/28/2020	4/27/2021
Amplifier	ITGA	ITPA-301	1701010003 30014	3/4/2021	3/3/2022
Bi-conical antenna	SunAR	JB1	A030818	4/10/2020	4/9/2021
Attenuator	JYEBAO	FAT-NM5NF5T62GW6	ATT001	3/24/2020	3/23/2021
Coaxial cable	SUHNER	SUCOFLEX 104	MY371154	7/16/2020	7/15/2021
Coaxial cable	SUHNER	SUCOFLEX 104	803600	7/16/2020	7/15/2021
Coaxial cable	SUHNER	SUCOFLEX 104	801734	7/16/2020	7/15/2021
test software	Audix	E3	20180316b	NA	NA

Harmonic and Flicker Emissions, DIP					
Instrument	Manufacturer	Model No.	Serial No.	Calibration Date	Valid Date
Power source	N4L	N4A30	91J-12901	2/18/2021	2/17/2022
Voltage drop simulator	EMCLioncel	VDS-1103	21101	2/18/2021	2/17/2022
Adjust power module	EMCLioncel	RGL-232	21101	2/18/2021	2/17/2022
Flicker Impedance Network	N4L	IMP323	91G-12804	12/8/2020	12/7/2021
power Analyzer	N4L	PPA5531	166-05417	12/8/2020	11/7/2021
Test software	N4L	IEC_Soft	2.6	NA	NA

ESD					
Instrument	Manufacturer	Model No.	Serial No.	Calibration Date	Valid Date
ESD Simulator	NoiseKen	ESS-S3011A	ESS1848144	2/23/2021	2/22/2022
ESD Gun	NoiseKen	GT-30RA	ESS1848164	2/23/2021	2/22/2022

RS					
Instrument	Manufacturer	Model No.	Serial No.	Calibration Date	Valid Date
Signal generator	Keysight	N5171B	MY57281132	3/4/2021	3/5/2022
Electric field probe	Narda	EP 601	711WX80850	2/26/2021	2/25/2023
Power sensor	Keysight	U2004A	MY57420018	3/4/2021	3/3/2022
Power Amplifier	fflight communication	NTWPA-0810200E	18103222	NA	NA
Power Amplifier	fflight communication	NTWPA-106050	18113274	NA	NA
Bi-log Antenna	SunAR	ATL80M1G	351399	NA	NA
Double log antenna	Schwarzbeck	STLP9149	627	NA	NA
test software	Audix	I2	20181211	NA	NA

EFT					
Instrument	Manufacturer	Model No.	Serial No.	Calibration Date	Valid Date
EFT Burst Generator	EMCLioncel	EFT-406CB	180803	2/17/2021	2/16/2022
Coupling Decoupling Networks	EMCLioncel	EFT-433CB	180803	2/17/2021	2/16/2022
EMC clamp	EMCLioncel	EFTC	18071802	2/17/2021	2/16/2022

SURGE					
Instrument	Manufacturer	Model No.	Serial No.	Calibration Date	Valid Date
Surge controller	EMCLioncel	SCU-614A+	0180202	NA	NA
Surge generator	EMCLioncel	LSG-510CB+	0171101	2/18/2021	2/17/2022
coupling Device Network	EMCLioncel	CDN-5310P	0180302	2/18/2021	2/17/2022
Surge ethernet CDN	3C TEST	CDN-405AF8	ES1011301	NA	NA

CS					
Instrument	Manufacturer	Model No.	Serial No.	Calibration Date	Valid Date
Signal generator	Keysight	N5171B	MY57281132	3/4/2021	3/3/2022
Power Amplifier	fflight communication	NTWPA-4K0100	18103215	NA	NA
100W attenuator	JPT	JPTATT-03-6	ATT17001	3/12/2021	3/11/2022
Couple device network	EMC Liconcel	CDN-M5-32	181001	3/10/2021	3/9/2022
Couple device network	EMC Liconcel	CDN-M3-16	181103	3/10/2021	3/9/2022
Couple device network	EMC Liconcel	CDN-M2-16	018074	3/10/2021	3/9/2022
EM Clamp	FRANKONIA	EMCL-20	18101672-0113	3/10/2021	3/9/2022
Power sensor	Keysight	U2004A	MY57420018	3/4/2021	3/3/2022
test software	Audix	I2	20181211	NA	NA

PFM					
Instrument	Manufacturer	Model No.	Serial No.	Calibration Date	Valid Date
power frequency magnetic	EMCLioncel	PMF-801C-C	180801	2/18/2021	2/17/2022
Magnetic coil	EMCLioncel	PMF-801C-A	180903	2/18/2021	2/17/2022

Note:NA mean is no calibration required.


15. Measurement Uncertainty

The assessed measurement uncertainty with a suitable coverage factor K to ensure 95% confidence level for the normal distribution are shown as below, the values are in table.

Please note that the test facility, environment and personal training minimize uncertainty of measurement due to the factor, the test results to determine refer to standard requirement, the measurement uncertainty values are not considered into the test data to determine the results.

Electromagnetic Interference			
Measurement Item	Measurement Frequency	Polarization	Uncertainty
Conducted Emission	150 kHz ~ 30 MHz	LINE / NEUTRAL	± 3.47dB
Radiated Emission	30 MHz ~ 1,000 MHz	Vertical / Horizontal	± 4.4 dB
	1,000 MHz ~ 6,000 MHz	Vertical / Horizontal	± 5.99 dB
Electromagnetic Susceptibility			
Measurement	Item	Uncertainty	
Electrostatic Discharges (ESD)	--	Rise time Tr ± 12.7% ns Peak current Ip ± 3.46% A Current at 30 ns ± 3.46% ns Current at 60 ns ± 3.46% ns	
Radiated RF electromagnetic Fields (Level Setting)	--	± 2.48dB	
Electrical Fast Transients and bursts	--	CDN V peak ± 9.4% V Rise time ±4.8% ns Clamp V peak ±8.6% V Rise time ±3.06% ns	
Surges	--	V peak = ± 8.6% V Rise time = ± 8.3% ns	
Conducted Disturbances, induced by RF fields	--	M2/M3/M5 ± 1.144 dB Clamp ± 2.094 dB	
Power-frequency Magnetic Field	--	Current ± 3.69 % A Magnetic file ± 1%	
Voltage Dips, Interruptions, and variations	--	± 10% V	

16. Attachment 1 – Photographs of EUT



View 3



View 4

